



November 2, 2021

NE Estimate #: 11090

Seagen, Inc.

Attn: Chibuzor Ejimofor
21823 30th Drive Southeast
Bothell, WA 98021

Project: Seattle Genetics B6 Lab E150
Subject: Add (1) Electrical standby receptacle for freezer

Chi,

Thank you for the opportunity to submit a proposal for the B6 E150 standby receptacle project. Below is a detailed description of our scope of work.

Scope of work:

1. Nelson to provide and install (1) new dedicated single phase 208v, 15A standby circuit in Rm E150 from Standby Panel 2SL13 located in the mezzanine. Conduit to be routed overhead through the Lab accessible ceiling and up through the ceiling. Includes new breaker.
2. Provide new conduit supports as necessary for this scope of work.
3. Provide and install (1) new NEMA 6-15R red single receptacles in Rm E150. Receptacles shall be flush mounted in existing wall mounted wiremold. Layout to be provided by Seagen.
4. Pricing includes updated panel schedules and as-built drawings.
5. Pricing includes research, coordination, permits, inspections, and supervision.
6. Pricing is based on work being performed during normal working hours (6am – 2:30pm). Any work outside of these hours will require a pricing adjustment.

Total Proposal: \$ 6,362.00

Clarifications and Exclusions:

1. Cutting and patching of sheet rock is excluded.
2. All work will be done on a straight time basis. No Overtime is included.
3. Nelson is not responsible for damaged to ceiling tiles.
4. Nelson will assist with coordination and planning.
5. Sales tax is not included

Please contact me if you have any questions

Thank you,

Daniel Bowers
Project Manager